

数 量 計 算 表				
工 種	規 格	計	算	数 量
舗装撤去工				
舗装切断	As t = 15cm以下	舗装展開図より	140.2	140 m
舗装版破碎	As t = 10cm以下	舗装展開図・数量調書より	175.5	176 m ²
殻運搬	As廃材	175.5*0.04=	7.0	7 m ³
処分工	AS	7.02*2.35=	16.5	17 t
舗装工				
不陸整正	粒調碎石M-25	舗装展開図・数量調書より	175.5	176 m ²
表層工	再生密粒度20F	舗装展開図・数量調書より	175.5	176 m ²
安全費				
交通誘導員B			4	4 人

[illegible]