

数 量 計 算 書					大松1号線	
工 種	種 別	規 格	計 算	単位	数 量	
撤去工						
舗装撤去工						
	舗装版切断		舗装展開図より29.07	29.1	m	29
	舗装版破砕		撤去計算書より963.5	963.5	m2	964
	殻運搬	L=28.6km AS殻	963.5*0.05	48.2	m3	48
	殻処分	塩沢産業 上田工場	48.2*2.35	113.3	t	113
土工						
作業土工						
	掘削		土量計算書より653.8	653.8	m3	650
	床掘		土量計算書より97.8	97.8	m3	100
	埋戻	発生土	度量計算書より46.1	46.1	m3	50
	土砂等運搬	L=20.6km	653.8+97.8-46.1/0.9	700.4	m3	700
	整地			700.4	m3	700
側溝工						
自由勾配側溝工（縦断用）						
	自由勾配側溝	300*300型	縦断用	174.0	m	174
	甲蓋	300型	(174/2-18)*2	138.0	枚	138
	グレーチング蓋	300型	174/10	17.4	枚	18
自由勾配側溝工（横断用）						
	自由勾配側溝	300*300型	横断用	8.0	m	8
	グレーチング蓋	300型	8/2	4.0	枚	4
土留付自由勾配側溝工						
	自由勾配側溝	300*300型	土留付	8.0	m	8
	自由勾配側溝	300*500型	土留付	8.0	m	8
	自由勾配側溝	300*700型	土留付	8.0	m	8
	自由勾配側溝	300*900型	土留付	8.0	m	8
	自由勾配側溝	300*1100型	土留付	8.0	m	8

数 量 計 算 書					
				大松1号線	
工 種	種 別	規 格	計 算	単位	数 量
	甲蓋	300型	(40/2-4)*2 32.0	枚	32
	グレーチング蓋	300型	40/10 4.0	枚	4
舗装工					
	表層工	t=5cm 再生密粒度As20F	面積計算書より963.5 963.5	m2	964
	不陸整正	補足材なし	(路盤施工部) 舗装計算書より720.0 720.0	m2	720
	不陸整正	補足材あり	963.5-720.0 243.5	m2	244
	上層路盤工	t=15cm M-40	面積計算書より720.0 720.0	m2	720
	下層路盤工	t=20cm RC-40	面積計算書より720.0 720.0	m2	720
	下層路盤工	t=55cm RC-40	土量計算書より720.0 720.0	m2	720
区画線設置工					
	区画線設置	(機・労)のみ	ペイント式 実線 W=15 c m 1405.0	m	1405
	区画線設置	(材料費のみ)	ペイント式 実線 白 W=15 c m 298	m	298
	区画線設置	(機・労)のみ	溶融式 実線 白 W=45 c m 19.0	m	19
	区画線設置	(材料費のみ)	溶融式 実線 白 W=45 c m 4	m	4
	路側カラー標示	W=45cm	W=45cm*3 舗装展開図より149.0*3 447.0	m	447
	路側カラー標示	W=15cm	W=15cm*1 舗装展開図より149.0 149.0	m	149

土 量 計 算 書								大松1号線					
測 点	断 面 積 (㎡)								距 離 (m)	土 量 (㎡)			
	掘削 C1	床掘 C2	埋戻 B1			掘削 C1	床掘 C2	埋戻 B1			掘削 C1	床掘 C2	
61.75	1.36	0.41	0.24										
69.75	1.66	0.29	0.39		1.51	0.35	0.32		8.0	12.1	2.8	2.6	
80.0	2.29	0.41	0.24		1.98	0.35	0.32		10.3	20.4	3.6	3.3	
82.07	4.84	0.90	0.44		3.57	0.66	0.34		2.1	7.5	1.4	0.7	
99.5	3.64	0.46	0.27		4.24	0.68	0.36		17.4	73.8	11.8	6.3	
120.0	3.89	0.49	0.19		3.77	0.48	0.23		20.5	77.3	9.8	4.7	
140.0	3.97	0.49	0.19		3.93	0.49	0.19		20.0	78.6	9.8	3.8	
160.0	3.52	0.52	0.19		3.75	0.51	0.19		20.0	75.0	10.2	3.8	
176.24	3.62	0.58	0.15		3.57	0.55	0.17		16.2	57.8	8.9	2.8	
180.0	3.60	0.59	0.19		3.61	0.59	0.17		3.8	13.7	2.2	0.6	
199.5	3.73	0.48	0.18		3.67	0.54	0.19		19.5	71.6	10.5	3.7	
220.0	6.31	1.07	0.60		5.02	0.78	0.39		20.5	102.9	16.0	8.0	
230.36	5.83	1.00	0.52		6.07	1.04	0.56		10.4	63.1	10.8	5.8	
								計	168.7	653.8	97.8	46.1	

取 壊 し 計 算 書													
大松1号線													
測 点	断 面 積 (㎡)								距 離 (m)	土 量 (㎡)			
	舗装破碎 W5				舗装破碎 W5					舗装破碎 W5			
61.75	2.00												
69.75	2.00				2.00				8.0	16.0			
80.0	3.00				2.50				10.3	25.8			
82.07	6.15				4.58				2.1	9.6			
99.5	6.15				6.15				17.4	107.0			
120.0	6.15				6.15				20.5	126.1			
140.0	6.15				6.15				20.0	123.0			
160.0	6.15				6.15				20.0	123.0			
176.24	6.15				6.15				16.2	99.6			
180.0	6.15				6.15				3.8	23.4			
199.5	6.15				6.15				19.5	119.9			
220.0	6.15				6.15				20.5	126.1			
230.36	6.15				6.15				10.4	64.0			

面積計算書										大松1号線			
測 点									距離 (m)				
	表層工 W1	不陸整正 W2	上層路盤 W3	下層路盤 W4	表層工 W1	不陸整正 W2	上層路盤 W3	下層路盤 W4		表層工 W1	不陸整正 W2	上層路盤 W3	下層路盤 W4
61.75	2.00	2.00	2.00	2.00									
69.75	2.00	2.00	2.00	2.00	2.00	2.00	2.00	2.00	8.0	16.0	16.0	16.0	16.0
80.0	3.00	3.00	3.00	3.00	2.50	2.50	2.50	2.50	10.3	25.8	25.8	25.8	25.8
82.07	6.15	6.15	6.15	6.15	4.58	4.58	4.58	4.58	2.1	9.6	9.6	9.6	9.6
99.5	6.15	6.15	4.10	4.10	6.15	6.15	5.13	5.13	17.4	107.0	107.0	89.3	89.3
120.0	6.15	6.15	4.10	4.10	6.15	6.15	4.10	4.10	20.5	126.1	126.1	84.1	84.1
140.0	6.15	6.15	4.10	4.10	6.15	6.15	4.10	4.10	20.0	123.0	123.0	82.0	82.0
160.0	6.15	6.15	4.10	4.10	6.15	6.15	4.10	4.10	20.0	123.0	123.0	82.0	82.0
176.24	6.15	6.15	4.10	4.10	6.15	6.15	4.10	4.10	16.2	99.6	99.6	66.4	66.4
180.0	6.15	6.15	4.10	4.10	6.15	6.15	4.10	4.10	3.8	23.4	23.4	15.6	15.6
199.5	6.15	6.15	4.10	4.10	6.15	6.15	4.10	4.10	19.5	119.9	119.9	80.0	80.0
220.0	6.15	6.15	6.15	6.15	6.15	6.15	5.13	5.13	20.5	126.1	126.1	105.2	105.2
230.36	6.15	6.15	6.15	6.15	6.15	6.15	6.15	6.15	10.4	64.0	64.0	64.0	64.0
								計	168.7	963.5	963.5	720.0	720.0