

数 量 計 算 表 (全体)					
施工名・種別	工 種	寸法・規格等	数 量 計 算		数 量
道路工					
道路土工					
掘削工	掘削	すきとり厚平均16cm 土砂	舗装面積計算表より(218.5+454.7+70.9)*0.16	119.0	119 m3
	土砂等運搬	小規模 DID区間なし 4.0km以下 バックホウ 山積0.8m3(平積0.6m3)	掘削より119.0	119.0	119 m3
	整地	残土受入れ地での処理	掘削より119.0	119.0	119 m3
舗装工					
舗装撤去工	舗装版切断	15cm以下	舗装展開図より3.5*3.0	10.5	11 m2
	舗装版破碎	既設舗装厚3cm 障害なし 15cm以下	舗装撤去計算書より231.7+482.3+74.4	788.4	788 m2
舗装準備工	不陸整正	補足材 なし	舗装面積計算表より218.5+454.7+70.9	744.1	744 m2
アスファルト舗装工	下層路盤(車道・路肩部)	1層施工 RC40-0	不陸整正より744.1	744.1	744 m3
	表層(車道・路肩部)	3.0m超 再生密粒度As20F t=4cm	舗装面積計算書より211.8+441.0+69.2	721.7	722 m2
産業廃棄物処理工					
産業廃棄物運搬工	殻運搬	15.8km (株)SHIOSAWA	舗装版破碎より788.4*0.03	23.7	24 m3
産業廃棄物処理工	アスファルト塊処分費		23.7*2.35	55.6	56 t

舗装撤去計算書 (1工区)

位 置	舗装幅	路盤幅	平均舗装幅	平均路盤幅	距 離	舗装面積		控除
pt. 0.0	3.500							
pt. 20.0	3.500		3.50		20.0	70.0		
pt. 40.0	3.500		3.50		20.0	70.0		
pt. 60.0	3.500		3.50		20.0	70.0		
pt. 66.2	3.500		3.50		6.2	21.7		
pt.								
pt.								
pt.								
pt.								
pt.								
pt.								
pt.								
				距離 計	66.2			
小 計						231.7		
控除合計								
合 計						231.7		m ²
採用数値						232		m ²

舗装撤去計算書 (2工区)

位 置	舗装幅	路盤幅	平均舗装幅	平均路盤幅	距 離	舗装面積		控除
pt. 0.0	3.500							
pt. 20.0	3.500		3.50		20.0	70.0		
pt. 40.0	3.500		3.50		20.0	70.0		
pt. 60.0	3.500		3.50		20.0	70.0		
pt. 80.0	3.500		3.50		20.0	70.0		
pt. 100.0	3.500		3.50		20.0	70.0		
pt. 120.0	3.500		3.50		20.0	70.0		
pt. 137.8	3.500		3.50		17.8	62.3		
pt.								
pt.								
pt.								
pt.								
				距離 計	137.8			
小 計						482.3		
控除合計								
合 計						482.3		m ²
採用数値						482		m ²

舗装撤去計算書 (3工区)

位 置	舗装幅	路盤幅	平均舗装幅	平均路盤幅	距 離	舗装面積		控除
pt. 0.0	5.000							
pt. 5.8	3.500		4.25		5.8	24.7		
pt. 20.0	3.500		3.50		14.2	49.7		
pt.								
pt.								
pt.								
pt.								
pt.								
pt.								
pt.								
pt.								
pt.								
				距離 計	20.0			
小 計						74.4		
控除合計								
合 計						74.4		m ²
採用数値						74		m ²

舗装面積計算書 (1工区)

位 置	舗装幅	路盤幅	平均舗装幅	平均路盤幅	距 離	舗装面積	路盤面積	控除
pt. 0.0	3.200	3.300						
pt. 20.0	3.200	3.300	3.20	3.30	20.0	64.0	66.0	
pt. 40.0	3.200	3.300	3.20	3.30	20.0	64.0	66.0	
pt. 60.0	3.200	3.300	3.20	3.30	20.0	64.0	66.0	
pt. 66.2	3.200	3.300	3.20	3.30	6.2	19.8	20.5	
pt.								
pt.								
pt.								
pt.								
pt.								
pt.								
pt.								
				距離 計	66.2			
小 計						211.8	218.5	
控除合計								
合 計						211.8	218.5	m ²
採用数値						212	218	m ²

舗装面積計算書 (2工区)

位 置	舗装幅	路盤幅	平均舗装幅	平均路盤幅	距 離	舗装面積	路盤面積	控除
pt. 0.0	3.200	3.300						
pt. 20.0	3.200	3.300	3.20	3.30	20.0	64.0	66.0	
pt. 40.0	3.200	3.300	3.20	3.30	20.0	64.0	66.0	
pt. 60.0	3.200	3.300	3.20	3.30	20.0	64.0	66.0	
pt. 80.0	3.200	3.300	3.20	3.30	20.0	64.0	66.0	
pt. 100.0	3.200	3.300	3.20	3.30	20.0	64.0	66.0	
pt. 120.0	3.200	3.300	3.20	3.30	20.0	64.0	66.0	
pt. 137.8	3.200	3.300	3.20	3.30	17.8	57.0	58.7	
pt.								
pt.								
pt.								
pt.								
				距離 計	137.8			
小 計						441.0	454.7	
控除合計								
合 計						441.0	454.7	m ²
採用数値						441	455	m ²

舗装面積計算書 (3工区)

位 置	舗装幅	路盤幅	平均舗装幅	平均路盤幅	距 離	舗装面積	路盤面積	控除
pt. 0.0	5.000	5.000						
pt. 5.8	3.200	3.300	4.10	4.15	5.8	23.8	24.1	
pt. 20.0	3.200	3.300	3.20	3.30	14.2	45.4	46.9	
pt.								
pt.								
pt.								
pt.								
pt.								
pt.								
pt.								
pt.								
				距離 計	20.0			
小 計						69.2	70.9	
控除合計								
合 計						69.2	70.9	m ²
採用数値						69	71	m ²